

# BOARD OF SECONDARY EDUCATION : ODISHA : CUTTTACK

## TENDER CALL NOTICE

No : 6334 (Engg. Section) Date : 30/10/2024

Sealed Tenders from intending agencies are hereby invited by the undersigned for the work repair and maintenance work of Store Building of BSE Odisha, Cuttack as per the specification noted below. Tender should be submitted in the Engineering Section of the Board on or before 12.11.2024 by 4.00 pm. The tender will be open on 13.11.2024 at 1.00 pm. The Tenderer should have valid contractor license, Registration Certificate under G.S.T. and PAN card. The name off the work should be subscribed on the top of the envelopes containing the Tender. The rates are to be quoted both as figure and words in each item per unit as indicated on the schedule. The Work is required to be completed within fifteen days from the date of issuance of work order from this office.

Authority reserves the right to cancel any or all Tenders without assigning any reason thereof.

Sl. No.	Description of Item	Qty.	Unit	Rate in Rs.
1	Filling floor plinth with sand well watered and rammed with all cost and labour T&P etc. Complete.	8.53	cum	
2	Cement Concrete in Prop (1:4:8) using 4C.M. size BHC B Gr. Metal with all cost and labour T&P etc complete.	4.28	cum	
3	Cement concrete in prop (1:2:4) using 12mm size BHC B Gr. Chips with all cost and Labour T&P etc. complete	2.99	cum	
4	Dismantling and removing old damage cement plaster from inside and outside walls etc. complete	140.8	cum	
5	16mm cement plaster in prop (1:6) over wall surface with all cost and labour T&P etc. Complete.	140.80	Sqm.	
6	12mm thick cement plaster in Prop(1:3) or ceiling etc. complete.	42.81	Sqm.	
7	Dismantling Old damage Brick/Stone wall under 3.00 mtr. & clean the area etc. complete.	10.37	Cum	
8	Fly Ash Brick Masonry in Cement mortar(1:4) using Fly Ash Brick of size(25X12X8)cm super structure for kitchen slab etc. Complete.	1.84	Cum	
9	Providing casting of 6cm size RCC Slab for kitchen stand with all cost and labour T&P etc. complete.	2.85	Sqm	
10	16mm thick cement plaster in prop (1:6) over super structure etc. complete.	29.82	Sqm	
11	Supplying fitting and fixing of Granite Tiles size above 0.40 Sqm (2'1" X 2'-1") (10mm to 20mm) thick with all cost and labour T&P etc. complete.	4.25	cum	
12	Supplying fitting and fixing of vitrified floor tiles of size 600 x 600mm of approved make conforming to IS 13755 laid on 20mm thick cement mortar (1:4) and finishing joints with white cement etc. complete.	75.61	Sqm	
13	Supplying fitting and fixing of tile in backdado skirting and riser of steps on 12 mm thick .M bed (1:3) ceramic wall tiles (20 cmx30cm)/ (20cmx20cm) etc. complete.	22.06	Sqm	
14	Providing fitting and fixing of MS Window grills including primering with Red Oxide primer etc. Complete.	273.91	Kg.	
15	Providing fitting and fixing of aluminium sliding window fully glazed of aluminium framed made up section No-9778,4095,4096,9777,3994 with 5mm thick glass or Act sheet etc. Complete.	4.75	Sqm	
16	Dismantling and removing old damage grading concrete and cleaning the roof surface etc. complete.	54.46	Sqm	
17	4 cm thick grading concrete in prop (1:2:4) with 12mm and 6mm size Gr. CB Chips with all cost and labour T&P etc. complete.	54.46	Sqm	

18	Distemping two coats with Oil Bound Distemper over wall surface with all cost and labour T&P etc. complete.				118.20	Sqm	
19	Painting two coats with weather seal coat over out side wall surface with all cost and labour T&P etc. complete.				99.72	cum	
20	Supplying all materials Labour T&P for providing and fixing to wall or ceiling and floor PVC/GI Pipes constructing of AST MD-17.85/89 sch-80 of the following nominal size fittings and clamps including making good the wall etc all complete as per specification and direction of Engg-in-charge.						
	a	25mm dia PVC pipe SCH-80		=	20.00	Mtrs	
	b.	110mm dia PVC SWR(6kg/cm) <sup>2</sup>		=	15.00	Mtrs	
	c.	110mm dia SWR TEE with door		=	4.00	Nos.	
	d.	110mm dia PVC SWR Door Bend		=	4.00	Nos.	
	e.	110mm dia SWR P trap		=	4.00	Nos.	
	f.	110mm dia SWR Single TEE with door		=	4.00	Nos.	
21	Supply all materials; labour T&P for fitting using of PH fixtures including cost, tax, conveyance etc all complete.						
	a	Fitting & fixing of 15mm CP Angular Stop Cock		=	3.00	Nos.	
	b	125mm dia CP Gritting		=	4.00	Nos.	
	c	15mm dia twin 2way bibcock		=	1.00	Nos.	
	d	Fitting & fixing of Health Faucet with 8mm dia 1.2mtr long flexible tube & wall hook		=	1.00	Nos.	
	e	PVC waste pipe 40mm long		=	3.00	Nos.	
	f	CP Soap holder		=	2.00	Nos.	
	g	450 mm dia glass mirror with CP Screw		=	2.00	Nos.	
	h	Fitting & fixing of CP Towel Ring		=	2.00	Nos.	
	i	Fitting & Fixing of 15mm CP Pillor Cock		=	2.00	Nos.	
	j	15mm C.P. Concealed Stop Cock		=	2.00	Nos.	
	k	125mmx450 mm cp glass self		=	2.00	Nos.	
	l	20 mmx450 mm long cp towel rail		=	2.00	Nos.	
	m	M Seal		=	1.00	Kg	
22	Supply all materials, labour T&P for fitting using of PH fixtures including cost, tax, conveyance etc all complete.						
	a	10 ltr capacity PVC L/L system		=	1.00	Nos.	
	b	Basin pedestal premium standard		=	1.00	Nos.	
	c	EWC with P/S trap white with plastic seat cover		=	1.00	Nos.	
	d	15 mm dia revolving shower		=	1.00	Nos.	
	e	Stainless steel Kitchen sink conforming to IS 13983 size 610x510x200 mm		=	1.00	Nos.	

(Total Twentytwo Items only)

*[Signature]*  
Secretary

Memo No : 6335 ..... Date : 30/10/2024.....

Copy forwarded to :-

The Section Officer, Engineering Section for information and necessary action. He is requested to display one copy on the office notice board for wide publication.

*[Signature]*  
Secretary

B.S.E., Odisha, Cuttack.